

# AGUA CALIENTE BAND OF CAHUILLA INDIANS






#### Reservation Established

- 1876 Executive Order by President U.S. Grant
  - Only Section 14, & East ½ of Section 22
- 1877 Reservation expanded into checkerboard by President Hayes
  - Even-numbered sections for the Tribe
  - Southern Pacific Railroad owned the odd-numbered sections (1862 Pacific Railway Act)
- □ 32,000+ acres set aside for the Reservation









#### Indian Canyons Trading Post

- 700sq. ft. building located 2 miles from the electrical grid
- Open 7 days a week (weekends only during summer)
- Power was provided by an aging propane generator
- Soaring maintenance and operation costs/reliability issues
- Noisy/trailer backup diesel generator put into fulltime use
- Multiple options considered in 2008
  - 2005 BIA Mineral Assessment grant
  - 2007 DOE First Steps grant







### Trading Post Solar Project

- ☐ Completed in 2 Phases 2009-10
- 8.25kW Off-grid Solar System
- 30 PV Panels
- 7.5kW backup diesel generator
- □ 1-2 Day Battery Backup (48V)
- Fully Automated












#### Project Challenges/Lessons Learned

- 24/7 365 days/year operational requirement
- Site restrictions
- Built-in redundancy
- "Hands free"
- Remote monitoring





- Limited options
- Compatibility issues
- System sizing
- Troubleshooting issues
- Cellular Internet connection problems





### Heritage Plaza Project

- □ Parking lot reconstruction with \$1.8M in Tribal Transportation Program funding:
  - Replace asphalt surface with concrete
  - Install carport shade structures
  - Relandscape with drought tolerant plantings
  - Project to be completed in 2 phases
- Carport shade structures were designed to be "solar ready"
- DOE grant funding pursued to install 76.9kW solar system on the carports







#### Heritage Plaza Solar Project

- □ \$240,000 Project; 50/50 match DOE Grant & Tribal Funds
- 79.95kW System 246 Solarworld PV Panels (325W ea)
- 99% power offset for \$22,000 annual electric bill
- Installation complete, permit signed off, & system turned on
- Functioning as designed absent Net Metering credit
- Interconnection Agreement Application submitted to SCE
- □ Payback with grant funding in ~5 years



# Phase 1 Complete





# Solar Project in Phase 1






#### Phase 2 Under Construction






# Solar Monitoring Software





## SCE Electricity Readings







# Questions?

#### **Todd Hooks**

Director of Economic Development
Agua Caliente Band of Cahuilla Indians
760-883-1350
thooks@aguacaliente-nsn.gov

#### Dan Malcolm

Planning Manager
Agua Caliente Band of Cahuilla Indians
760-883-1945
dmalcolm@aguacaliente-nsn.gov